

New RepairBase Line Item additions for the 8-9-2019 Update

Bathroom Items – Cabinets & Vanities

- Remove & Reset Vanity W/Top & Faucet - up to 36"
- Remove & Reset Vanity W/Top & Faucet - over 36"

Cabinets & Shelves – Bathroom Cabinets & Vanities

- Remove & Reset Vanity W/Top & Faucet - up to 36"
- Remove & Reset Vanity W/Top & Faucet - over 36"

Cabinets & Shelves – Kitchen Cabinets

- Remove & Reset Cabinets – Per Hour

Foundations – Foundations

- Concrete Epoxy Crack Repair - Caulking Gun Injection - Per LF
- Concrete Epoxy Crack Repair - Caulking Gun Injection - Minimum Charge
- Concrete Epoxy Crack Repair - Injections Under Pressure - Per LF
- Concrete Epoxy Crack Repair - Injections Under Pressure - Minimum Charge
- Concrete Epoxy Hole Repair - Poured Epoxy - Per Cubic Inch
- Concrete Epoxy Hole Repair - Poured Epoxy - Minimum Charge
- Underpin & Raise Concrete Foundation - Hydraulic Pressed 6" Diameter Concrete Pier - Does Not Include Inspection - Per Pier - up to 10 FT
- Underpin & Raise Concrete Foundation - Hydraulic Pressed 6" Diameter Concrete Pier - Does Not Include Inspection - Per Pier - Each Additional FT Over 10 FT
- Mudjacking - Raise Concrete Slab With Pressurized Grout Injection - Per 1" Diameter Hole - Assumes Area Is Ready To Drill - First Hole
- Mudjacking - Raise Concrete Slab With Pressurized Grout Injection - Per 1" Diameter Hole - Assumes Area Is Ready To Drill - Each Additional Hole

New RepairBase Line Item additions for the 8-9-2019 Update

Heating & Cooling – Boilers

- Replace Boiler Oil Tank - Horizontal - 275 Gallon - Includes new Legs, Gauge, Alarm, Fill Spout and Vent Cap - Does not include Removal or Disposal
- Replace Boiler Oil Tank - Vertical - 330 Gallon - Includes new Legs, Gauge, Alarm, Fill Spout and Vent Cap - Does not include Removal or Disposal
- Replace Boiler Oil Tank - Vertical - 275 Gallon - Includes new Legs, Gauge, Alarm, Fill Spout and Vent Cap - Does not include Removal or Disposal

Heating & Cooling – Furnaces

- Remove & Reset Floor Furnace
- Remove & Reset Forced Air Furnace
- Remove & Reset Wall Furnace

Heating & Cooling – Heat Pumps

- Replace Heat Pump - Packaged Through Wall Terminal Unit - 20000 BTU with electric heater - Does not Include Creating Wall Opening
- Replace Heat Pump - Packaged Through Wall Terminal Unit - 24000 BTU with electric heater - Does not Include Creating Wall Opening
- Replace Heat Pump - Packaged Through Wall Terminal Unit - 36000 BTU with electric heater - Does not Include Creating Wall Opening

Painting – Exterior – Exterior Walls

- Equipment Rental - Scaffolding - Exterior - 10 Ft Long x 5 FT Wide x 5 FT High - Per Week
- Equipment Rental - Scaffolding - Exterior - 10 Ft Long x 5 FT Wide x 10 FT High - Per Week
- Equipment Rental - Scaffolding - Exterior - 10 Ft Long x 5 FT Wide x 15 FT High - Per Week
- Equipment Rental - Scaffolding - Exterior - 10 Ft Long x 5 FT Wide x 20 FT High - Per Week
- Equipment Rental - Scaffolding - Exterior - 10 Ft Long x 5 FT Wide x 25 FT High - Per Week

Painting – Interior – Walls & Ceilings

New RepairBase Line Item additions for the 8-9-2019 Update

- Equipment Rental - Scaffolding - Interior - 6 FT Long x 29 Inch Wide x 6 FT High - Per Day
- Equipment Rental - Scaffolding - Interior - 6 FT Long x 29 Inch Wide x 6 FT High - Per Day - Each Additional 6 FT High Level
- Equipment Rental - Scaffolding - Interior - 6 FT Long x 29 Inch Wide x 6 FT High - Per Week
- Equipment Rental - Scaffolding - Interior - 6 FT Long x 29 Inch Wide x 6 FT High - Per Week - Each Additional 6 FT High Level

Preservation & Maintenance – Winterization

- Add Glycol Anti Freeze to Winterized Plumbing System - Per Gallon

Stairs & Steps – Balusters & Railings

- Replace Complete Stair Handrail System - Wood - Paint Grade - Includes, Baluster, Newel Post, Sub Rail, Handrail and Paint - Per LF
- Replace Complete Stair Handrail System - Wood - Stain Grade - Includes, Baluster, Newel Post, Sub Rail, Handrail and Stain - Per LF

Walls & Ceilings – Interior - Tile

- Install new - Underlayment - Cementitious Backer Board - up to 1/2" - Per SF

Walls & Fascia – Exterior - Stucco

- Replace Stucco - Includes Light Prep, Lathe, Base Coat, and Color Coat - Per SF
- Replace Parget Wall - 1 Coat - Includes light Prep - Does not include Lathe - Per SF
- Replace Parget Wall - 2 Coats - Includes light Prep - Does not include Lathe - Per SF
- Replace Parget Wall - 2 Coats with Lathe - Includes light Prep - Per SF